WATERDOWN TO FINCH PROJ	ECT	
Environmental Report		
ΔΡΡΕΝΠΙΥ Δ	CONSTRUCTION TYPICAL DRAWING	S
AI I LIIDIA A	CONSTRUCTION ITTICAL BRAVIING	

PROFILE - LOOKING DOWNSTREAM

CO-LOCATION WITH EXISTING/FOREIGN PIPELINES

NOTES:

- 1. THIS DRAWING REFLECTS "TRENCH AND SPOIL SIDE" TOPSOIL STRIPPING PROCEDURE.
- SALVAGE TOPSOIL OVER TRENCH AND UNDER THE SPOIL PILE AT LOCATIONS IDENTIFIED ON THE CONSTRUCTION ALIGNMENT SHEETS, OR AS DIRECTED BY ENVIRONMENTAL INSPECTOR.
- 3. TOPSOIL IN URBAN, COMMERCIAL, AND INDUSTRIAL AREAS WILL BE SEPARATED WHERE THERE IS A DISTINCT SOIL CHANGE. AG LAND TOPSOIL SEPARATION WILL BE TO A MAXIMUM OF 0.3m.
- 4. STOCKPILE TOPSOIL AS SHOWN OR IN CONFIGURATION APPROVED BY ENVIRONMENTAL INSPECTOR.
- 5. KEEP TOPSOIL CLEAN OF ALL CONSTRUCTION DEBRIS.
- 6. MAINTAIN A 1m SEPARATION OR AN INSTALLED MITIGATION MEASURE TO PREVENT SOIL MIXING.
- BREAKS / GAPS IN THE TOPSOIL PILES AND SUB-SOIL PILES SHOULD BE MADE AT LOCATIONS TO INSURE NATURAL DRAINAGE IS NOT IMPEDED.
- 8. DO NOT USE TOPSOIL FOR PADDING.
- 9. BACKFILLING TOPSOIL SHOULD BE DONE CAREFULLY TO MINIMIZE SCALPING OF THE EXISTING VEGETATION.
- 10. TEMPORARILY SUSPEND TOPSOIL HANDLING OPERATIONS DURING HIGH WIND AND WET CONDITIONS UNTIL MITIGATION MEASURES TO REDUCE WIND EROSION CAN BE IMPLEMENTED.
- 11. EXTRA TEMPORARY WORK SPACE MAY BE NECESSARY IN SPECIAL CIRCUMSTANCES.

WATERDOWN TO FINCH PROJECT

		*	UniversalP	gasu ATIONA				Imperial			
0		ISSUED FOR	. PERMIT		01/16/	2019	JW		Υ	O: 24255-507-TYP	
NO.		REVISI	ON		DA.	TE	CONSTRUCTION CONFIGURATI				
	SCALE	DATE	DRAWN	CHE	CKED	APPI	ROVED	PROJ. NO.	DRAWING NUMBER	SHEET	
	N.T.S.	09/10/2018	JMC	ŀ	IC	JW		24255	ONT-WF-SPPL-UP-KD-0006	1 OF 1	UPI DRAWING NO:

FILE INFO://HOU-FS1/HOU PROJECTS/24255/01500 ENG-DSN/507 GEOMATICS DSN/TYP-TYPICALS/ONT-WF-SPPL-UP-KD-0006.DWG;LAST SAVED BY: JOSEPH,CARDENAS ON 1/17/2019 12:36 PM

NOTES:

- 1. THIS DRAWING REFLECTS "TRENCH AND SPOIL SIDE" TOPSOIL STRIPPING PROCEDURE.
- SALVAGE TOPSOIL OVER TRENCH AND UNDER THE SPOIL PILE AT LOCATIONS IDENTIFIED ON THE CONSTRUCTION ALIGNMENT SHEETS, OR AS DIRECTED BY ENVIRONMENTAL INSPECTOR.
- 3. TOPSOIL IN URBAN, COMMERCIAL, AND INDUSTRIAL AREAS WILL BE SEPARATED WHERE THERE IS A DISTINCT SOIL CHANGE. AG LAND TOPSOIL SEPARATION WILL BE TO A MAXIMUM OF 0.3m.
- 4. STOCKPILE TOPSOIL AS SHOWN OR IN CONFIGURATION APPROVED BY ENVIRONMENTAL INSPECTOR.
- 5. KEEP TOPSOIL CLEAN OF ALL CONSTRUCTION DEBRIS.
- 6. MAINTAIN A 1m SEPARATION OR AN INSTALLED MITIGATION MEASURE TO PREVENT SOIL MIXING.
- BREAKS / GAPS IN THE TOPSOIL PILES AND SUB-SOIL PILES SHOULD BE MADE AT LOCATIONS TO INSURE NATURAL DRAINAGE IS NOT IMPEDED.
- 8. DO NOT USE TOPSOIL FOR PADDING.
- 9. BACKFILLING TOPSOIL SHOULD BE DONE CAREFULLY TO MINIMIZE SCALPING OF THE EXISTING VEGETATION.
- 10. TEMPORARILY SUSPEND TOPSOIL HANDLING OPERATIONS DURING HIGH WIND AND WET CONDITIONS UNTIL MITIGATION MEASURES TO REDUCE WIND EROSION CAN BE IMPLEMENTED.
- 11. EXTRA TEMPORARY WORK SPACE MAY BE NECESSARY IN SPECIAL CIRCUMSTANCES.

WATERDOWN TO FINCH PROJECT

		*	UniversalP	gasu Ationa			Imperial			
0	0 ISSUED FOR PERMIT		01/16/	2019	JW		TYPICAL CONVENTIONAL LA' RUCTION CONFIGUR	-		
NO.		REVISION			DA	ΤE	APPR.	CONST	RUCTION CONFIGUR	ATION 2
	SCALE	DATE	DRAWN	CHE	CKED	APPI	ROVED	PROJ. NO.	DRAWING NUMBER	SHEET
	N.T.S.	09/11/2018	JMC	H	IC		JW	24255	ONT-WF-SPPL-UP-KD-0007	1 OF 1

NOTES:

- 1. THIS DRAWING REFLECTS "TRENCH AND SPOIL SIDE" TOPSOIL STRIPPING PROCEDURE.
- SALVAGE TOPSOIL OVER TRENCH AND UNDER THE SPOIL PILE AT LOCATIONS IDENTIFIED ON THE CONSTRUCTION ALIGNMENT SHEETS, OR AS DIRECTED BY ENVIRONMENTAL INSPECTOR.

WORKING LAYOUT CONFIGURATION CO-LOCATION WITH TRANSMISSION LINES AND FOREIGN PIPELINE

- 3. TOPSOIL IN URBAN, COMMERCIAL, AND INDUSTRIAL AREAS WILL BE SEPARATED WHERE THERE IS A DISTINCT SOIL CHANGE. AG LAND TOPSOIL SEPARATION WILL BE TO A MAXIMUM OF 0.3m.
- 4. STOCKPILE TOPSOIL AS SHOWN OR IN CONFIGURATION APPROVED BY ENVIRONMENTAL INSPECTOR.
- 5. KEEP TOPSOIL CLEAN OF ALL CONSTRUCTION DEBRIS.
- 6. MAINTAIN A 1m SEPARATION OR AN INSTALLED MITIGATION MEASURE TO PREVENT SOIL MIXING.
- BREAKS / GAPS IN THE TOPSOIL PILES AND SUB-SOIL PILES SHOULD BE MADE AT LOCATIONS TO INSURE NATURAL DRAINAGE IS NOT IMPEDED.
- 8. DO NOT USE TOPSOIL FOR PADDING.
- 9. BACKFILLING TOPSOIL SHOULD BE DONE CAREFULLY TO MINIMIZE SCALPING OF THE EXISTING VEGETATION.
- 10. TEMPORARILY SUSPEND TOPSOIL HANDLING OPERATIONS DURING HIGH WIND AND WET CONDITIONS UNTIL MITIGATION MEASURES TO REDUCE WIND EROSION CAN BE IMPLEMENTED.
- 11. EXTRA TEMPORARY WORK SPACE MAY BE NECESSARY IN SPECIAL CIRCUMSTANCES.

WATERDOWN TO FINCH PROJECT

		*	UniversalP	cgasu Atletia			Imperial			
0 ISSUED FOR PERMIT		01/16	2019	JW		TYPICAL CONVENTIONAL LA				
NO.		REVISI	ON	DATE			CONST	RUCTION CONFIGUR	ATION 3	
	SCALE	DATE	DRAWN	CHE	CKED	APP	ROVED	PROJ. NO.	DRAWING NUMBER	SHEET
	N.T.S.	09/11/2018	JMC	HC J		JW	24255	ONT-WF-SPPL-UP-KD-0008	1 OF 1	

FILE INFO:/HOUFS1:HOU PROJECTS/24256/0:500 ENG-DSM:507 GEOMATICS DSM:TYP-TYPICALS/ONT-WF-SPPL-UP-KD-0:008 DWG:LAST SAVED BY: JOSEPH.CARDENAS ON 1/17/2019 12:39 PM

WORKING LAYOUT CONFIGURATION CO-LOCATION WITH TRANSMISSION LINES AND FOREIGN PIPELINE


NOTES:

- THIS DRAWING REFLECTS "TRENCH AND SPOIL SIDE" TOPSOIL STRIPPING PROCEDURE. 1.
- SALVAGE TOPSOIL OVER TRENCH AND UNDER THE SPOIL PILE AT LOCATIONS IDENTIFIED ON THE CONSTRUCTION ALIGNMENT SHEETS. 2. OR AS DIRECTED BY ENVIRONMENTAL INSPECTOR.
- 3. TOPSOIL IN URBAN, COMMERCIAL, AND INDUSTRIAL AREAS WILL BE SEPARATED WHERE THERE IS A DISTINCT SOIL CHANGE. AG LAND TOPSOIL SEPARATION WILL BE TO A MAXIMUM OF 0.3m.
- 4. STOCKPILE TOPSOIL AS SHOWN OR IN CONFIGURATION APPROVED BY ENVIRONMENTAL INSPECTOR.
- 5. KEEP TOPSOIL CLEAN OF ALL CONSTRUCTION DEBRIS.
- MAINTAIN A 1m SEPARATION OR AN INSTALLED MITIGATION MEASURE TO PREVENT SOIL MIXING. 6.
- 7. BREAKS / GAPS IN THE TOPSOIL PILES AND SUB-SOIL PILES SHOULD BE MADE AT LOCATIONS TO INSURE NATURAL DRAINAGE IS NOT IMPEDED.
- 8. DO NOT USE TOPSOIL FOR PADDING.
- 9. BACKFILLING TOPSOIL SHOULD BE DONE CAREFULLY TO MINIMIZE SCALPING OF THE EXISTING VEGETATION.
- TEMPORARILY SUSPEND TOPSOIL HANDLING OPERATIONS DURING HIGH WIND AND WET CONDITIONS UNTIL MITIGATION MEASURES TO 10. REDUCE WIND EROSION CAN BE IMPLEMENTED.
- EXTRA TEMPORARY WORK SPACE MAY BE NECESSARY IN SPECIAL CIRCUMSTANCES. 11.


WATERDOWN TO FINCH **PROJECT**

		*	UniversalP	gasu Ationa Ationa		Imperial				
0) ISSUED FOR PERMIT					2019	JW		TYPICAL CONVENTIONAL LA	-
NO.		REVISI	ON		DATE		APPR.	CONSTI	RUCTION CONFIGUR	ATION 4
SCALE [DATE	DRAWN	CHE	CKED	CKED APPI		PROJ. NO.	DRAWING NUMBER	SHEET
	N.T.S.	09/11/2018	JMC	H	IC) Jv		24255	ONT-WF-SPPL-UP-KD-0009	1 OF 1

FILE INFO://HOU-FS1/HOU PROJECTS/24255/01500 ENG-DSN/507 GEOMATICS DSN/TYP-TYPICALS/ONT-WF-SPPL-UP-KD-0009.DWG;LAST SAVED BY: JOSEPH,CARDENAS ON 1/17/2019 12:41 PM



Profile View



NOTES

- INSPECT BRIDGE OPENING PERIODICALLY AND FOLLOWING RAINFALLS OF OVER 1.5CM. REMOVE ANY DEBRIS RESTRICTING FLOW AND DEPOSIT IT AT AN UPLAND SITE OUTSIDE OF FLOODPLAIN.
- IF PHYSICAL CIRCUMSTANCES PROHIBIT WOOD OR METAL RAMPS, EARTHEN RAMPS MAY BE USED AS APPROVED.
- 3. INSPECT BRIDGE ELEVATION SO BRIDGE REMAINS SUPPORTED ABOVE HIGH BANK AND DOES NOT SINK INTO BANK.
- 4. THE BRIDGE MUST SPAN FROM TOP OF BANK TO TOP OF BANK.

- 5. IN THE EVENT OF SETTLING, ADDITIONAL SUPPORT WILL BE ADDED.
- 6. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSPECTED AND MAINTAINED IN ACCORDANCE WITH THE COMPANY'S ENVIRONMENTAL MITIGATION PLAN


For environmental review purposes only.




Typical Temporary Span Type Bridge (Removed after Construction) Waterdown to Finch Project



MPLS: ERM_TYP_Span_Bridge.vsd Scale: NTS Revised: 2019/01/31 Drawn By: GIS







CONSTRUCTION PROCEDURE NOTES:

- 1. FLAG WETLAND BOUNDARIES PRIOR TO CLEARING.
- NO REFUELING OF MOBILE EQUIPMENT IS ALLOWED WITHIN 30 METERS OF WETLAND. PLACE "NO FUELING" SIGN POSTS 30 METERS BACK FROM WETLAND BOUNDARY. REFUEL STATIONARY EQUIPMENT AS PER SPCC PLAN.
- 3. INSTALL TEMPORARY SLOPE BREAKER UPSLOPE WITHIN 15 METERS OF WETLAND BOUNDARY AS DIRECTED BY THE ENVIRONMENTAL INSPECTOR.
- RESTRICT ROOT GRUBBING TO ONLY THE AREA OVER THE DITCHLINE.
- 5. TOPSOIL STRIPPING SHALL NOT BE REQUIRED IN SATURATED SOIL CONDITIONS.
- 6. UTILIZE AMPHIBIOUS EXCAVATORS (PONTOON MOUNTED BACKHOES) OR TRACKED BACKHOES SUPPORTED BY FABRICATED TIMBER MATS OR FLOATS, TO EXCAVATE TRENCH. IF FABRICATED TIMBER MATS ARE USED FOR STABILIZATION, THE BACKHOE SHALL GRADUALLY MOVE ACROSS THE WETLAND BY MOVING THE MAT FROM IMMEDIATELY BEHIND TO IMMEDIATELY IN FRONT OF THE BACKHOE'S PATH.
- AVOID ADJACENT WETLANDS. INSTALL SEDIMENT BARRIERS (STRAW BALES AND/OR SILT FENCE) AT EDGE OF R.O.W. AND ALONG WETLAND EDGE AS REQUIRED.
- 8. FABRICATE PIPE IN A STAGING AREA OUTSIDE THE WETLAND AS INDICATED ON THE CONSTRUCTION DRAWINGS.
- 9. LEAVE HARD PLUGS AT THE EDGE OF WETLAND UNTIL JUST PRIOR TO PIPE PLACEMENT.
- FLOAT PIPE IN PLACE, LOWER-IN, INSTALL TRENCH PLUGS AT WETLAND EDGES OR AS DIRECTED BY THE ENVIRONMENTAL INSPECTOR AND BACKFILL IMMEDIATELY.
 - 1. REMOVE ANY MATS OR FILL CONSISTING OF NON-NATIVE MATERIAL FROM WETLANDS UPON COMPLETION.
- RESTORE GRADE TO NEAR PRE-CONSTRUCTION TOPOGRAPHY AND INSTALL TEMPORARY AND PERMANENT STRUCTURES TO MAINTAIN STABILITY AS NEEDED.
- 13. WETLANDS WILL NOT TYPICALLY BE SEEDED. HOWEVER, IF THE SITE IS DRY AND IF DIRECTED BY THE ENVIRONMENTAL INSPECTOR, THE DISTURBED AREAS SHALL BE SEEDED TO STABILIZE THE AREA UNTIL INDIGENOUS SPECIES IS RE-ESTABLISHED.


WATERDOWN TO FINCH PROJECT

			*	UniversalP	cgasu ationa				Imperial		
	0 ISSUED FOR PERMIT		01/16/	01/16/2019 JW		FLOC	TYPICAL DDED WETLAND CRO	OSSING			
I	NO.		REVISI	ON		DATE		APPR.		(PUSH/PULL)	
ſ		SCALE	DATE	DRAWN	CHE	CKED	KED APPE		PROJ. NO.	DRAWING NUMBER	SHEET
		N.T.S.	09/12/2018 JMC HC J		JW	24255	ONT-WF-SPPL-UP-HD-0102	1 OF 1			





Plan View (Not to Scale)



Profile (Not to Scale)

NOTES:

- 1. ACQUIRE AND MARK ADDITIONAL TEMPORARY WORKSPACE.
- 2. SET UP EQUIPMENT BACK FROM THE EDGE OF THE WATERCOURSE; DO NOT CLEAR OR GRADE WITHIN BUFFER ZONE EXCEPT ALONG THE WORK SIDE, IF TEMPORARY VEHICLE CROSSING IS INSTALLED.
- 3. EXCAVATE BELLHOLE. STORE SPOIL ON OPPOSITE SIDE OF RIGHT-OF-WAY.
- 4. COMPLETE BORING AND TIE-IN TO MAINLINE.
- 5. PUMP BELLHOLE DRY IF SEEPAGE BECOMES A PROBLEM. DEWATER BELLHOLES ONTO STABLE, VEGETATED LAND, NOT DIRECTLY BACK INTO WATERCOURSE.
- 6. BACKFILL AND COMPACT.


SOURCE: ADAPTED FROM PIPELINE ASSOCIATED WATERCOURSE CROSSINGS 3RD EDITION 2005

For environmental review purposes only



Typical Waterbody Crossing - Bore Method Waterdown to Finch Project





CONSTRUCT DEWATERING STRUCTURE TO ACCOMMODATE ANTICIPATED PUMPING RATES.

NOTES:


- 1. CONSTRUCT DEWATERING STRUCTURE TO ACCOMMODATE ANTICIPATED PUMPING RATES.
- $2.\ \mbox{USE}$ A FILTER BAG AT THE DISCHARGE HOSE END.
- 3. IF SILT FENCE IS USED, ENDS MUST BE WRAPPED TO JOIN TWO SECTIONS.
- 4. INSTALL SILT FENCE 5CM ABOVE TOP OF STRAW BALE (IF USED), AND ANCHOR A MINIMUM OF 20CM STRAIGHT DOWN.
- 5. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE USED, INSPECTED, AND MAINTAINED IN ACCORDANCE WITH THE PROJECTS EROSION AND SEDIMENT CONTROL PLAN.

For environmental review purposes only.



Typical Straw Bale and Filter Bag Dewatering Structure Waterdown to Finch Project






For environmental review purposes only



Typical Stabilized Stream Crossing Waterdown to Finch Project



MPLS: Drawn By: GIS



Note:

PLACE JUTE BLANKET A MINUMUM OF 30CM UNDER RIP RAP. EXTEND JUTE BLANKET FROM MEAN HIGH WATER LEVEL TO BEHIND BANK.

For environmental review purposes only



Typical Final Stream Bank Stabilization -**Rip Rap & Erosion Control**

Waterdown to Finch Project

